



BRUHAT BANGALORE MAHANAGARA PALIKE

KODIGEHALLI SUBDIVISION

WARD NO.07, Byatarayanapura

**Name of work Improvements to drains roads in
maruthi farm, in Amruthanagara A sector in
ward no.07, Byatarayanapura**

Est cost: 85.00 lakhs

Name of Work:- Improvements to drains roads in maruthi farm, in Amruthanagara A sector in ward no.07, Byatarayanapura

			Estimate Cost:					85.00 Lakhs	
S.N	DESCRIPTION OF WORK	Unit	N	L	B	D	QTY	RATE	AMOUNT
1	2	3	4	5	6	7	8	9	10
1	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. Pg No.143.Item No.19.1)								
	Desilting of existing drains								
	maruthi farm main road		2.00	140.00	0.60	0.60	100.80		
	1st cross		2.00	29.00	0.60	0.60	20.88		
	2nd cross		1.00	35.00	0.60	0.60	12.60		
	3rd cross		2.00	40.00	0.60	0.60	28.80		
	4th cross		2.00	50.00	0.60	0.60	36.00		
	muniramayya layout cross road 1		1.00	65.00	0.60	0.60	23.40		
	3rd main		2.00	150.00	0.60	0.60	108.00		
	muniramayya layout cross road 2		1.00	50.00	0.60	0.60	18.00		
	2nd main		2.00	300.00	0.60	0.60	216.00		
	Narayanaswamy layout 6th cross		1.00	40.00	0.60	0.60	14.40		
	Narayanaswamy layout 7th cross		1.00	40.00	0.60	0.60	14.40		
	For Pit		45.00	3.14*0.8*0.8		3.00	67.82		
	(3.14x0.6x0.)/4 x 3.0			4					
	Overburden		58.00	2.00	1.20	1.00	139.20		
					TOTAL		800.30	137.80	110281.89
	Basic Rate:	cum	130.00						
	Area Weightage @ 6%		7.80						
	Total		137.80						

2	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC aggregates @ 220kgs, with crushed 40mm and down size graded granite metal coarse mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials labour, HOM curing, form works, scaffolding and centering complete as per specification.										
		Below kerb	maruthi farm main road	2.00	140.00	0.45	0.15	18.90			
		1st cross		2.00	29.00	0.45	0.10	2.61			
		2nd cross		1.00	35.00	0.45	0.10	1.58			
		3rd cross		2.00	40.00	0.45	0.10	3.60			
		4th cross		2.00	50.00	0.45	0.10	4.50			
		munitramayya layout cross road 1		1.00	65.00	0.45	0.10	2.93			
		Maruthi form 5th cross		2.00	86.00	0.45	0.10	7.74			
		3rd main		2.00	150.00	0.45	0.15	20.25			
		munitramayya layout cross road 2		1.00	50.00	0.45	0.10	2.25			
		2nd main		2.00	300.00	0.45	0.15	40.50			
		Narayanaswamy layout 6th cross		1.00	40.00	0.45	0.15	2.70			
		Narayanaswamy layout 7th cross		1.00	40.00	0.45	0.15	2.70			
		Basic Rate: cum			5115.00			5421.90	597764.48		
		Area Weightage @ 6%			306.90						
		Total			5421.90						
3	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 7.5 cm thick (Pg No.27, Item No.5.31.1)										
		BS SLAB DRAIN	maruthi farm main road	2.00	115.00	1.35		310.50			
		1st cross		2.00	25.00	1.35		67.50			
		2nd cross		1.00	30.00	1.35		40.50			
		3rd cross		2.00	35.00	1.35		94.50			
		4th cross		2.00	40.00	1.35		108.00			
		munitramayya layout cross road 1		1.00	55.00	1.35		74.25			
		3rd main		2.00	70.00	1.35		189.00			
		munitramayya layout cross road 2		1.00	100.00	1.35		135.00			
		2nd main		2.00	40.00	1.35		108.00			
		munitramayya layout cross road 2		1.00	200.00	1.35		270.00			
		Narayanaswamy layout 7th cross		1.00	40.00	1.35		54.00			
		Basic Rate: Sqm			700.00			1451.25	742.00	1076827.50	
		Area Weightage @ 6%			42.00						
		Total			742.00						

4	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not less than 1800 kg/m ³ and having a minimum average compressive strength 4.00 N/mm ² confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing complete as per specifications. KBS No.5.4 with all lead and lift, loading and unloading and all other incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work. (Pg No.27, Item No.5.28)							
	For raising side walls of drain							
	maruthi farm main road		2.00	140.00	0.10		28.00	
	1st cross		2.00	29.00	0.10		5.80	
	2nd cross		2.00	35.00	0.10		7.00	
	3rd cross		2.00	40.00	0.10		8.00	
	4th cross		2.00	50.00	0.10		10.00	
	muniswamappa layout		2.00	65.00	0.10		13.00	
	Maruthi form 5th cross		2.00	150.00	0.10		30.00	
	3rd main		2.00	50.00	0.10		10.00	
	muniswamappa layout cross road 2		2.00	300.00	0.10		60.00	
	Narayanaswamy layout 6th cross		2.00	40.00	0.10		8.00	
	Narayanaswamy layout 7th cross		2.00	40.00	0.10		8.00	
					TOTAL	187.80	859.66	161445.00
	Basic Rate:	Sqm	811.00					
	Area Weightage @ 6%		48.66					
	Total		859.66					

5	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 10cms thick. (Pg No.27, Item No.5.31.2)	COVERING SLAB									
		maruthi farm main road	2.00	120.00	0.75		180.00				
		1st cross	2.00	25.00	0.75	37.50					
		2nd cross	1.00	30.00	0.75	22.50					
		3rd cross	2.00	35.00	0.75	52.50					
		4th cross	2.00	40.00	0.75	60.00					
		munitramayya layout cross road 1	1.00	50.00	0.75	37.50					
		3rd main	2.00	120.00	0.75	180.00					
		munitramayya layout cross road 2	1.00	50.00	0.75	37.50					
		2nd main	2.00	250.00	0.75	375.00					
		Narayanaswamy layout 6th cross	1.00	35.00	0.75	26.25					
		Narayanaswamy layout 7th cross	1.00	35.00	0.75	26.25					
		TOTAL				1035.00	966.72	1000556.00			
		Basic Rate:	Sqm	912.00							
		Area Weighthage @ 6%		54.72							
		Total		966.72							
6	KSRB 5-8.1: Providing one line dressing to granite stone slabs/granite stone masonry as per specifications.KBS 5-1.13	5.13									
		maruthi farm main road	2.00	140.00	0.75	210.00					
		1st cross	2.00	29.00	0.75	43.50					
		2nd cross	1.00	35.00	0.75	26.25					
		3rd cross	2.00	40.00	0.75	60.00					
		4th cross	2.00	50.00	0.75	75.00					
		munitramayya layout cross road 1	1.00	65.00	0.75	48.75					
		3rd main	2.00	150.00	0.75	225.00					
		munitramayya layout cross road 2	1.00	50.00	0.75	37.50					
		2nd main	2.00	300.00	0.75	450.00					
		Narayanaswamy layout 6th cross	1.00	40.00	0.75	30.00					
		Narayanaswamy layout 7th cross	1.00	40.00	0.75	30.00					
		TOTAL				1236.00	950.82	1175214.00			
		Basic Rate:	Sqm	897.00							
		Area Weighthage @ 6%		53.82							
		Total		950.82							

7 Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete. Pg No. 27, Item No.5.29.1								
	maruthi farm main road		2.00	140.00			280.00	
	1st cross		2.00	29.00			58.00	
	2nd cross		1.00	35.00			35.00	
	3rd cross		2.00	40.00			80.00	
	4th cross		2.00	50.00			100.00	
	muniramayya layout cross road 1		1.00	65.00			65.00	
	Maruthi form 5th cross		2.00	86.00			172.00	
	3rd main		2.00	150.00			300.00	
	muniramayya layout cross road 2		1.00	50.00			50.00	
	2nd main		2.00	300.00			600.00	
	Narayanaswamy layout 6th cross		1.00	40.00			40.00	
	Narayanaswamy layout 7th cross		1.00	40.00			40.00	
							1820.00	
			TOTAL(total length/0.45)				4044.44	
							4045	467.46 1890876.00
	Basic Rate:	Nos	441.00					
	Area Weightage @ 6%		26.46					
	Total		467.46					
8 KSRB 5-9.1: Providing and applying ready mix priming coat over concrete / masonry, / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour complete as per specifications. Page No. 124 / Item No. 15.80								
			4044.44		0.45		1820.00	
					TOTAL		1820.00	39.22 71381.00
	Basic Rate:	sqm	37.00					
	Area Weightage @ 6%		2.22					
	Total		39.22					
9 Providing and fixing MS Grating 260x260 mm (Page No.1X, SI No.234, code No.0771)								
	For shoulder drains		370.00				370.00	
					TOTAL		370.00	84.75 31357.50
	Basic Rate:	Nos	84.75					
	Total		84.75					

[illegible]

17	Direction and place identification signs upto 0.9 sqm size Board - Providing and erecting direction and place identification retro-reflectorised signs as per revised IRC : 67-2012 made of high intensity grade sheeting vide clause 800.1.3, fixed over aluminium sheeting, 2mm thick with area not exceeding 0.9 sqm supported on a mild steel single angle iron post 75x75x6mm firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 45x45x60cm, 60cm below ground level as per approved drawing complete as per specifications. MORTH Specification No.801 Type IV sheeting (Page no.179, item no.24.3.1) 24.3							
	Name boards		125.00	0.6	0.45	33.75		
	Small size		125.00	0.6	0.15	11.25		
		Nos				45.00	7274.78	327365.10
18	Providing and applying readymix priming coat concrete / masonry / asbestos cement sheet /plasterd surface including preparing the surface after thoroughly cleaning of oil grease dirt and other foreign matter and sand papering cost of materials labour as per specifications (page no.124, item no.15.80)							
	Name boards		125*2	0.6	0.45	67.50		
			125*2	0.6	0.15	22.50		
	pipes		125.00	0.31	2.6	100.75		
	Existing boards		125*2	0.6	0.45	67.50		
			125*2	0.6	0.15	22.50		
			125.00	0.31	2.6	100.75		
						381.50	39.22	14962.43
	Basic Rate:	sqm	37.00					
	Area Weightage @ 6%		2.22					
	Total		39.22					
19	Supply MS. Pipe. Code No. 256.SI No.301. Pg No.X. 25MM DIA & 2.5MM THICK							
		MTR	125.00	2.6	14.5	4712.50	84.75	399384.38
	Basic Rate:	Nos	84.75					
	Total		84.75					
20	Painting on Steel surface :- Providing and applying two coats of ready mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications. complete as per specifications. MORTH Specification No.803(page no.180, item no.24.8.1)							
	New boards		125.00	0.31	2.6	100.75		
			125*2		0.6	150.00		
	Old boards		125.00	0.31	2.6	100.75		
			125*2		0.6	150.00		
						501.50	76.32	38274.48
	Basic Rate:	sqm	72.00					
	Area Weightage @ 6%		4.32					
	Total		76.32					

AE/3E
TA
No. 39 / 19-20 Dated: 16/03/2020
Registered as SE(Y)/TS/ 39 / 19-20
Job Code No. 007-19-000011
Under P 3522
85009.000/-
Eight Five Lakhs only
Total sanctioned for Rs.

AE/3E
16/03/20
ADMINISTRATIVE APPROVAL
Accorded For Rs. 85.00 Lacs only
Head of Ac. P 3522
Div. Ref. No. 110 / 19-20
Date 9-3-2020
EE(BTP) 2/03

Asst. Engineer
Ward no. 7
Bhaly N.D.

Asst. Exe. Engineer
Kodigehalli Sub-division
B.B.M.P.

Executive Engineer
Byatrayanapura Division
B.B.M.P.


1) This is certified that the work spot comes under BBMP limits only.
2) The rates are as per CSR of 2018-19 year of PWD Bangalore Circle.

20	Painting new latter and figures any shade with synthetic enamel paint black or Hindi (Matras commas and the like not to be measured and paid for half latter shall be counted as half) (page no. 181, item no. 24.9)	125.00	7	45	39375.00				
21	New boards	125.00	7	45	39375.00				
22	old boards	125.00	7	45	39375.00				
23	Basic Rate:	cm	1.00						
24	Area Weightage @ 6%		0.06						
25	Total		1.06						
26	Sub Total				78750.00	1.06	83475.00		
27	Add 12% GST charges								910700.60
28	Miscellaneous charges								127.73
29	Total								8500000.00

2nd main = 3500m

Improvements to drains roads in Maruthi farm, in

Maruthanagara 'A' sector in Ward no. 07, byadarayanapura.




Asst. M. N. D.


A.E. (W)

Assistant Executive Engineer,
Kodigehalli Sub Division,
Bruhat Bangalore Mahanagara Palika,
Bangalore - 560 092

Improvements to drainage roads in Marothi farm in Amrotha-nagara At sector in ward no.07, byatarayanapura.



CROSS-SECTION OF DRAIN (BS SLAB)



CROSS-SECTION OF CULVERT

Asstt. N.D
AET (2)

my
Assistant Executive Engineer
Kodigehalli Sub Division
Bruhat Bangalore Mahanagara Palik
Bangalore - 560 092